



Clarification No. 2

October 14, 2021

RE: Component 2: Reconstruction of Dock Face – Phase 1 at Facility One

FROM: Tina Perkins, Project Administrator
Toledo – Lucas County Port Authority
One Maritime Plaza, 7th floor
Toledo, Ohio 43604-1866
Website: toledoportauthority.org
P. (419)243-8251

TO: Plan Holders

This clarification to the addendum supplements and amends the original drawings and specifications. It shall be considered in preparing proposals and shall become a part of the Contract Documents. **Acknowledge receipt of this Clarification in the space provided on the Form of Proposal.** Failure to do so may subject Bidder to disqualification.

BID DOCUMENT CLARIFICATION

- **Lift Station**
 - The storm water drains by gravity into STM 26 at an invert of 573.06'. The pump is to be installed to accommodate lifting the storm water and discharging to an 18" pipe with an invert of 575.36'. The 18" pipe would then discharge to Duck Creek by gravity. The pump should be capable of discharging at a rate of 2.4 cfs. The 18" pipe should be Class V Reinforced Concrete.

- **Asphalt Concrete Intermediate Course**
 - Clarification to Addendum No. 1, question 16
 - The asphalt concrete intermediate course shall be Type 2.

END OF CLARIFICATION NO. 2